

The Spectral Amplitude of Stellar Convection and its Scaling in the High-Rayleigh-Number Regime

Nicholas A. Featherstone

Department of Applied Mathematics, University of Colorado, Boulder, CO 80309-0526

`feathern@colorado.edu`

Bradley W. Hindman

JILA & Department of Astrophysical and Planetary Sciences, University of Colorado,
Boulder, CO 80309-0440

Received _____; accepted _____

ABSTRACT

Convection plays a central role in the dynamics of any stellar interior, and yet its operation remains largely-hidden from direct observation. As a result, much of our understanding concerning stellar convection necessarily derives from theoretical and computational models. The Sun is, however, exceptional in that regard. The wealth of observational data afforded by its proximity provides a unique testbed for comparing convection models against observations. When such comparisons are carried out, surprising inconsistencies between those models and observations become apparent. Both photospheric and helioseismic measurements suggest that convection simulations may overestimate convective flow speeds on large spatial scales. Moreover, many solar convection simulations have difficulty reproducing the observed solar differential rotation due to this apparent overestimation. We present a series of 3-dimensional (3-D) stellar convection simulations designed to examine how the amplitude and spectral distribution of convective flows are established within a star’s interior. While these simulations are non-magnetic and non-rotating in nature, they demonstrate two robust phenomena. When run with sufficiently high Rayleigh number, the integrated kinetic energy of the convection becomes effectively independent of thermal diffusion, but the spectral distribution of that kinetic energy remains sensitive to both of these quantities. A simulation that has converged to a diffusion-independent value of kinetic energy will divide that energy between spatial scales such that low-wavenumber power is overestimated, and high-wavenumber power is underestimated relative to a comparable system possessing higher Rayleigh number. We discuss the implications of these results in light of the current inconsistencies between models and observations.

Subject headings: Stars: kinematics and dynamics, Sun: helioseismology, Sun: interior, Sun: magnetic fields, Stars: interior, Stars: fundamental parameters

1. Introduction

Convection is a pervasive phenomenon within stars and serves as the principle transport mechanism by which fusion-generated energy is transmitted across significant portions of the stellar interior. This transport may occur primarily within a convective core, as in the case of massive stars, or within an outer convective envelope, as in cool stars such as the Sun. As that convection takes place within a rotating, electrically conductive plasma, it undoubtedly plays an active role in the generation of stellar magnetism. More specifically, rotation imbues convective motions with helicity which may serve to amplify magnetic fields through the so-called α -effect (e.g., Moffat 1978). Further, the propensity of convective flows to redistribute angular momentum—thereby driving a differential rotation—may also render convective motion central to the generation of coherent, global-scale magnetic fields through the Ω -effect (i.e., large-scale rotational shearing of the field).

Convection in the stellar context is thought to be highly turbulent; typical estimates for the Reynolds and Rayleigh numbers are 10^{13} and 10^{20} respectively (e.g., Ossendrijver 2003). These extreme parameters make stellar convection challenging to study, whether experimentally or theoretically. This challenge is compounded by the fact that such convection occurs within a rotating, magnetized environment.

Investigations into stellar convection are most readily initiated within the context of the Sun. The wealth of observational data afforded by the proximity of that star make it an ideal test bed against which predictions of stellar convection models may be tested and calibrated before extending those models to other stars. Despite the abundance of solar data, the convective motions central to its dynamo remain largely hidden from view in all but the shallowest layers of the convection zone. Whatever its detailed structure, that convection must satisfy two robust observational constraints: it must transport one solar luminosity’s worth of energy across the convection zone, and it must efficiently redistribute

angular momentum in order to sustain the Sun’s helioseismically inferred differential rotation.

Exploring the magnetohydrodynamical balances at work in stellar interiors has largely been the purview of three-dimensional (3-D), nonlinear, numerical convection simulations. In the case of the Sun, these simulations are often run by assigning solar values to most model variables, notably the rotation rate and the luminosity, while admitting diffusivities that are computationally tractable but also necessarily orders of magnitude larger than their intended microscopic counterparts (e.g., Brun et al. 2004; Ghizaru et al. 2010; Hotta et al. 2014). It is now becoming increasingly evident that such quasi-laminar simulations have succeeded in maintaining a solar-like differential rotation and energy flux in part due to the out-sized role played by diffusion in many of those models.

As advances in computational power have enabled the use of lower and ostensibly more stellar-like diffusivities, inconsistencies between models and observations have begun to arise. Notable among these are the so-called anti-solar states of differential rotation which exhibit an equator of retrograde rotation and polar regions of prograde rotation. Such states develop when the characteristic convective turnover time drops below some critical fraction of the rotation period (e.g., Gilman 1977; Glatzmaier & Gilman 1982). This transition occurs naturally in solar simulations as the level of diffusion is decreased (Featherstone & Miesch 2015), and it tends to arise even in those models that do not employ an explicit, Fickian diffusivity (Hotta et al. 2014). While almost certainly relevant within a broader stellar context (see e.g., Kővári et al. 2007), these anti-solar states stand at odds with the well-established internal rotation profile of the Sun (e.g., Thompson et al. 2003).

Further inconsistencies arise when the distribution of velocity power among different spatial scales is examined in detail. Photospheric observations and helioseismic observations of the deeper interior both suggest that numerical simulations may over-estimate the

amplitude of the solar convection on large spatial scales (Hanasoge et al. 2012; Lord et al. 2014). The helioseismic consensus concerning deep flows remains murky, however. Recent ring-analysis measurements of subsurface flows throughout the near-surface sheer layer exhibit good agreement with convection models (Greer et al. 2015). While the question of subsurface flow speeds remains an open question, we note that the time-distance measurements of Hanasoge et al. (2012), if confirmed, are particularly troubling as they suggest that convection on spatial scales larger than 70 Mm can be at most $5\text{--}6\text{ m s}^{-1}$. This stands in contrast to theoretical estimates based on gyroscopic pumping which suggest that convective flows must be at least 30 m s^{-1} on those spatial scales (Miesch et al. 2012). Weaker flows would have difficulty generating Reynolds stresses which are strong enough to maintain the solar differential rotation.

These theoretical and observational disagreements suggest that something fundamental, related to the transport of heat and angular momentum by magnetized convection, may be missing in stellar convection models. Until these issues can be resolved in the context of the Sun, for which we have such an abundance of observational data, the relationship of *any* stellar convection model to an actual star remains highly questionable.

We present a set of numerical experiments designed to examine how the structure and amplitude of the convective flow field is determined within a stellar interior. Specifically, we ask, *“How is the amplitude and spectral-power distribution of stratified convection related to the stellar luminosity and level of diffusion present in the system.”* For this paper, we address that question without considering the effects of rotation and magnetism which, while admittedly important, would substantially extend the parameter space of this already challenging study. We choose instead to focus our initial study on how density stratification, luminosity, and diffusivity relate to the amplitude and spatial power spectrum of the resulting convection. Our results demonstrate that the convective kinetic energy is

related to these three parameters through an unambiguous scaling relationship. In addition, we demonstrate that models run in the typical stellar-convection fashion may naturally overestimate low-wavenumber power in the convective power spectrum.

This paper is organized as follows. In §2 and §3, we discuss our numerical model and the parameter space explored in our numerical experiments. We then discuss our results in §4, followed by a discussion of their implications in §5.

2. Numerical Model

This study is based around a series of 3-D, nonlinear convection models run using the *Rayleigh* convection code, developed as a community code for the Computational Infrastructure for Geodynamics (CIG). *Rayleigh* simulates convection using the spectral transform approach described in Glatzmaier (1984). We employ a spherical geometry and represent the horizontal variation of all variables along spherical surfaces using spherical harmonics $Y_\ell^m(\theta, \phi)$. Here, ℓ is the spherical harmonic degree, and m is the azimuthal mode order. In the radial direction, we employ a Chebyshev collocation method, expanding all variables using Chebyshev polynomials $T_n(r)$, where n is the degree of the Chebyshev polynomial. Derivatives are calculated accurately within the spectral representation by exploiting the properties of these two sets of basis functions. We work on a de-aliased grid, such that the number of collocation points in each dimension is larger than the corresponding number of spectral modes by a factor of 3/2.

As our approach is pseudo-spectral in nature, nonlinear terms are calculated in physical space after first transforming the relevant variables from the spectral configuration. Time-integration is carried out in the spectral configuration using a hybrid implicit-explicit approach. A Crank-Nicolson method is used for linear terms, and an Adams-Bashforth

approach is employed for the nonlinear terms. Both components of the time-stepping possess 2nd-order accuracy. Algorithmically, it is the parallelization of *Rayleigh*, which parallelizes efficiently on up to $O(10^5)$ cores, that differs significantly from that of Glatzmaier (1984). We have verified our particular implementation of that approach against two established benchmark tests, and we provide results from those tests in Appendix A.

Our study is concerned with convection as it manifests deep within stellar interiors, far removed from the photospheric surface where radiative processes may contribute considerably to the energetics of the convection. In such a region of the star, plasma motions are subsonic and perturbations to thermodynamic variables are small compared to their mean, horizontally-averaged values. Under such conditions, the anelastic approximation, which we choose to employ, provides a convenient means of describing the system’s thermodynamics (Gough 1969; Gilman & Glatzmaier 1981).

When using this approximation, thermodynamic variables are linearized about a spherically symmetric, time-independent reference state with density $\bar{\rho}$, pressure \bar{P} , temperature \bar{T} , and specific entropy \bar{S} . Fluctuations about this state are denoted, without overbars (ρ , P , T , and S). A further consequence of the anelastic approximation is that the mass flux is solenoidal, reducing the continuity equation to

$$\nabla \cdot (\bar{\rho} \mathbf{v}) = 0, \quad (1)$$

where $\mathbf{v} = (v_r, v_\theta, v_\phi)$ is the velocity vector expressed in spherical coordinates. The lack of any time derivative in Equation (1) means that sound waves are naturally filtered out as a consequence of this approach. The divergence-free constraint for the mass flux is enforced by projecting \mathbf{v} onto poloidal and toroidal streamfunctions (W and Z respectively), such that

$$\bar{\rho} \mathbf{v} = \nabla \times \nabla \times (W \mathbf{e}_r) + \nabla \times (Z \mathbf{e}_r). \quad (2)$$

The unit vector in the radial direction is indicated by \mathbf{e}_r . The momentum equation is given

by

$$\bar{\rho} \frac{D\mathbf{v}}{Dt} = -\bar{\rho} \nabla \frac{P}{\bar{\rho}} - \frac{\bar{\rho} S}{c_p} \mathbf{g} - \nabla \cdot \mathcal{D}, \quad (3)$$

where \mathbf{g} is the gravitational acceleration, and c_p is the specific heat at constant pressure. In writing the momentum equation this way, we have employed the so-called Lantz-Braginsky-Roberts approximation, which is exact for adiabatic reference states such as those employed in this study (Lantz 1992; Braginsky & Roberts 1995). The viscous stress tensor \mathcal{D} is given by

$$\mathcal{D}_{ij} = -2\bar{\rho}\nu \left[e_{ij} - \frac{1}{3}(\nabla \cdot \mathbf{v})\delta_{ij} \right], \quad (4)$$

where e_{ij} is the strain rate tensor. The kinematic viscosity is denoted by ν , and δ_{ij} is the Kronecker delta. Our thermal energy equation is given by

$$\bar{\rho}\bar{T} \frac{DS}{Dt} = \nabla \cdot [\kappa \bar{\rho} \bar{T} \nabla S] + 2\bar{\rho}\nu \left[e_{ij}e_{ij} - \frac{1}{3}(\nabla \cdot \mathbf{v})^2 \right] + Q, \quad (5)$$

where the thermal diffusivity is denoted by κ . Sources of internal heating and cooling are encapsulated by the functional form of Q . A linearized equation of state closes our set of equations and is given by

$$\frac{\rho}{\bar{\rho}} = \frac{P}{\bar{P}} - \frac{T}{\bar{T}} = \frac{P}{\gamma \bar{P}} - \frac{S}{c_p}, \quad (6)$$

assuming the ideal gas law

$$\bar{P} = \mathcal{R} \bar{\rho} \bar{T}. \quad (7)$$

The specific heat at constant pressure is denoted by c_p , \mathcal{R} is the gas constant, and γ is the adiabatic index of the gas.

3. The Numerical Experiment

We have constructed a series of 63 model stellar convection zones designed to explore how the convective kinetic energy depends on three model parameters: the degree of density

TABLE 1

Variable Input Parameters	
Param	Value
M_i	1.989×10^{33} g
ρ_i	1.805×10^{-1} g cm $^{-3}$
c_p	3.5×10^8
n	1.5
N_ρ	1,2,3,4
r_i	5.0×10^{10} cm
r_o	6.586×10^{10} cm

Note. — Polytropic reference state parameters for all cases. The reference state prescription differs between simulations in the value of N_ρ chosen only.

stratification, level of thermal diffusion, and the stellar luminosity. A detailed listing of all model parameters may be found in Appendix B.

Each of our models is constructed using a polytropic background state following Jones et al. (2011). This approach has the advantage that the thermodynamic background may be specified analytically, making it easily reproducible. Our background may be completely specified by seven numbers: the inner radius of the shell r_i , the outer radius of the shell r_o , the polytropic index n , the number of density scale heights occurring within the shell N_ρ , the mass interior to the shell M_i , the density at the inner boundary ρ_i , and the specific heat c_p . With the exception of N_ρ , these values are the same for all experiments reported on here, and we list them in Table 1. All background states are adiabatically stratified, possessing a polytropic index n of 1.5 and an adiabatic index γ of 5/3. Further details of the polytropic background are provided in Appendix C for completeness.




Fig. 1.— Polytypic reference states used in this study. (a) Radial variation of density corresponding to each value of N_ρ used in our simulations (indicated by line coloring). The $N_\rho = 3$ cases closely resemble the Model-S density stratification (black diamonds; Christensen-Dalsgaard et al. 1996). (b) Radial variation of thermal energy flux that must be transported by convection and thermal conduction for each value of N_ρ (coloring as in panel a). Fluxes have been normalized by the stellar flux. The flux corresponding to Model S is indicated by the dashed black line.

We have chosen to examine a range of density stratifications (N_ρ) for this study. One consequence of this approach is that shells with a higher degree of density stratification possess a lower mass than their more weakly stratified counterparts. We note that when constructed using the parameters from Table 1, the thermodynamic background state closely resembles that of the Sun for the value $N_\rho = 3$. We plot the density variation with radius for each of our four chosen values of N_ρ , along with that from a standard solar model (Model S; Christensen-Dalsgaard et al. 1996), in Figure 1a.

For all simulations, we have adopted impenetrable and stress-free boundary conditions such that

$$v_r(r = r_i, r_o) = \frac{\partial(v_\theta/r)}{\partial r} \Big|_{r=r_i, r_o} = \frac{\partial(v_\phi/r)}{\partial r} \Big|_{r=r_i, r_o} = 0. \quad (8)$$

The radial entropy gradient is forced to vanish at the lower boundary of the convection zone, and the entropy perturbations are forced to vanish at the upper boundary, with

$$\frac{\partial S}{\partial r} \Big|_{r=r_i} = 0, \quad S(r_o) = 0. \quad (9)$$

Thus, there is no diffusive entropy flux across the lower boundary. Instead, heat enters the system through internal deposition by Q , which drops to zero at the upper boundary. In all simulations, we adopt a functional form of Q that depends only on the background pressure profile such that

$$Q(r, \theta, \phi) = \alpha(\bar{P}(r) - \bar{P}(r_o)). \quad (10)$$

The normalization constant α is chosen so that

$$L_\star = 4\pi \int_{r_i}^{r_o} Q(r) r^2 dr, \quad (11)$$

where L_\star is the stellar luminosity. The thermal energy flux $F(r)$ that convection and conduction must transport across a spherical surface at radius r is then given by

$$F(r) = \frac{1}{r^2} \int_{r_i}^r Q(x) x^2 dx. \quad (12)$$

The value of L_\star is varied between simulations, as is the value of N_ρ , and that of the diffusion coefficients ν and κ . In all instances, we have adopted a Prandtl number $Pr = \nu/\kappa$ of unity.

The functional form of Q means that as the value of N_ρ is increased, the heating becomes more focused near the lower boundary. This behavior is illustrated in Figure 1*b*, where we have plotted $F(r)$, normalized by the stellar flux at each radius. Our prescription for the internal heating in the $N_\rho = 3$ cases resembles that derived using solar temperature and opacity values tabulated in Model S (dashed line). We note that small differences, comparable to those observed between reference states with differing values of N_ρ , do exist between the $N_\rho = 3$ case and the solar model. Those differences arise primarily from the fact that we have chosen the base of our model convection zones to lie at a radius of 5×10^{10} cm, somewhat higher than that of the Sun. The results discussed in §4 suggest, however, that the functional form of the internal heating has little effect on the kinetic energy realized in our high-Rayleigh-number simulations.

At the upper boundary, heat exits the system via thermal conduction. There,

the steepness of the equilibrated entropy gradient is entirely dependent upon the thermodynamic background state, the value of the thermal diffusivity κ , and the chosen luminosity. Specifically, the time-averaged value of the entropy gradient must equilibrate to

$$\left. \frac{\partial S}{\partial r} \right|_{r=r_o} = \frac{L_\star}{4\pi r_o^2 \kappa \rho(r_o) T(r_o)} \quad (13)$$

3.1. Non-dimensionalization

All simulations were run in a manner analogous to one commonly used in solar convection studies (e.g., Brun et al. 2004; Ghizaru et al. 2010; Hotta et al. 2014, Featherstone & Miesch 2015). Namely, we have run these simulations using *dimensional* parameters for the equation coefficients, and we assign “stellar” values to those parameters, with the notable exception of the diffusivities. The values chosen for our diffusion coefficients are instead motivated purely by matters of computational feasibility; thus they are necessarily orders of magnitude larger than the microscopic values. It is customary to suggest that this prescription for the diffusivity constitutes a form of subgrid-scale model, representing the mixing of heat and momentum by small-scale eddy motions that cannot be sufficiently resolved on the coarse computational grid. We make no such assertion here, and remark simply that our diffusivities are rather large when compared to stellar values. The diffusion coefficients ν and κ are taken to be constant values within each of our simulations. In particular, they possess no variation in radius.

Across our set of numerical convection experiments, we have varied the degree of thermal stratification (characterized by N_ρ), the luminosity of the star L_\star , and the thermal diffusivity κ . This three-dimensional parameter space may be collapsed by considering an appropriate non-dimensionalization of the system. As we have chosen a Pr of unity and have neglected the effects of rotation and magnetism, all runs may be well-characterized by a single non-dimensional number, the Rayleigh number.

For Boussinesq convection, the Rayleigh number is typically defined in terms of the temperature, but in our anelastic formulation, the thermal properties of the fluid are instead conveyed by entropy. Our simulations also differ from the classical Rayleigh-Bénard setup, which possesses fixed-temperature boundaries, in that we have effectively imposed a flux by specifying Q and the entropy boundary conditions of Equation (9). It is thus appropriate for our system to define a flux Rayleigh number in terms of entropy. Throughout this paper, the term *Rayleigh number* will be used to refer to a *flux* Rayleigh number Ra_F , which we define as

$$Ra_F = \frac{\tilde{g}\tilde{F}H^4}{c_p\tilde{\rho}\tilde{T}\nu\kappa^2}. \quad (14)$$

We choose to use volume averages for all quantities possessing a tilde in the definition of Ra_F , making it a bulk Rayleigh number. Here H is a typical length scale, and we choose the shell depth $r_o - r_i$ as its value. Our numerical experiments span the range $10^3 \leq Ra_F \leq 3 \times 10^7$. Each simulation was initialized using a small random thermal perturbation, evolved until the kinetic energy reached a statistically steady state, and further evolved for at least one thermal diffusion time further following the onset of that statistically steady state.

4. Survey of Results

4.1. Kinetic-Energy Scaling and Spectral Distribution

We begin our discussion of the convective energetics by looking at the integrated kinetic energy KE , defined as

$$KE = \frac{1}{2} \int_V \bar{\rho}(r) |\mathbf{v}(r, \theta, \phi)|^2 dV. \quad (15)$$

The relationship of KE to thermal diffusivity is illustrated in Figure 2a. There, we have plotted KE vs. κ^{-1} , using colored symbols to distinguish between the level of stratification




Fig. 2.— Dimensional and non-dimensional view of kinetic energy scaling. (a) Dimensional kinetic energy KE vs. κ^{-1} for all cases run with $L_\star = L_\odot$. Colored symbols indicate the level of density stratification. At sufficiently low κ , KE approaches a constant value within each N_ρ series. (b) Non-dimensional kinetic energy \widehat{KE} vs. flux Rayleigh number Ra_F for *all* cases (regardless of the value of L_\star). Colored symbols indicate N_ρ as in panel a. When viewed non-dimensionally, all N_ρ series collapse onto a single curve and approach an asymptotic scaling law with $\widehat{KE} \propto Ra_F^{0.694}$ (dashed line). The delineation between high- and low- Ra_F regimes is indicated by the dash-dotted line.

employed in each model. Each data point represents an average of 3000 days of simulation time. This is approximately one thermal diffusion time across the shell for those cases with $\kappa \geq 1 \times 10^{12}$ cm² s⁻¹. Only two of our models possess a lower value of κ (5×10^{11} cm² s⁻¹), but this averaging interval still encompasses several tens of convective overturning times. We have also omitted those cases run with a non-solar value of L_\star in this figure so that the general trend may be clearly seen. For each set of curves, the integrated KE rises until some critical value of κ is reached. Below this critical value of κ , KE asymptotes to a nearly constant value that is *essentially independent of the level of diffusion* κ . These simulations have thus reached a state of so-called turbulent free-fall (e.g., Spiegel 1971), which we discuss further in §5 of this paper. A fit to the low- κ data in Figure 2a yields the relationship

$$KE \propto \kappa^{-0.082 \pm 0.024}, \quad (16)$$

which is only weakly dependent on κ .

The point of transition to this asymptotic regime depends on N_ρ . More weakly stratified cases transition to the asymptotic regime at a lower value of κ than their more strongly stratified counterparts. In addition, the saturation level of KE may be weakly dependent on N_ρ , as evinced by the $N_\rho = 1$ curve (red). It is possible, however, that those weakly stratified cases are simply converging more slowly to the same value as the $N_\rho > 1$ cases. All cases with $N_\rho > 1$ converge to a similar value of KE .

The similarity of behavior in KE between systems with different N_ρ is made more readily apparent by examining how KE depends on the Rayleigh number Ra_F . In so doing, we choose a non-dimensional measure of the kinetic energy \widehat{KE} such that

$$\widehat{KE} \equiv \frac{H^2}{\kappa^2 M} KE. \quad (17)$$

The nondimensionalization has been carried out using the depth of the domain, the thermal diffusion timescale, and the mass M contained within the spherical shell (which is a function of N_ρ). In Figure 2b, we have plotted \widehat{KE} vs. Ra_F . When plotted in this fashion, all results fall along a similar curve that describes a power-law relationship between KE and Ra_F . Performing a least-squares fit to the high- Ra_F portion of this plot ($Ra_F \geq 10^5$), we find that

$$\widehat{KE} \propto Ra_F^{0.694 \pm 0.008}. \quad (18)$$

The measured value of the exponent is very close to $\frac{2}{3}$. This value indicates that beyond Ra_F of 10^5 , which we designate as the “high- Ra_F ” region of this curve, diffusion is no longer playing a substantial a role in determining the convective amplitudes.

While achieving a truly “stellar” value for the Rayleigh number is clearly impossible in a modern convection simulation, these results nevertheless imply a clear prerequisite for comparing any convection simulation against stellar observations. **Namely, a simulation’s parameters should place it well within the high- Ra_F region of Figure 2b before any comparison is made against actual data.**




Fig. 3.— Time-averaged velocity power spectra (dimensional) for all cases run using $L_\star = L_\odot$. Each row corresponds to a single value of N_ρ (indicated on the right), and each column corresponds to a single depth within the convective shell. Within each panel, spectra for all cases at that depth and N_ρ are displayed. Low- Ra_F cases are indicated in blue tones, and high- Ra_F cases in red tones. The highest- Ra_F case within each series is further indicated by the dashed, dark red line. As Ra_F is increased, power at low ℓ -values increases initially. At high Ra_F , it decreases as high-wavenumber power is generated at the expense of low-wavenumber power.

This result has interesting consequences for the relative spectral distribution of kinetic energy between high- and low- Ra_F systems. In Figure 3, we have plotted the kinetic-energy spectra for those cases in our study that possess the solar luminosity. Spectra are plotted at three depths in each simulation (1 depth per column). These depths are taken near the upper boundary, the mid-shell, and near the lower boundary. Different values of N_ρ correspond to different rows. Within each panel, all spectra for high- Ra_F runs at that N_ρ have been plotted. Low values of Ra_F , indicated by dark blue tones, have been plotted for the $N_\rho = 1$ cases in order to illustrate the trend for that region of parameter space. They have been largely omitted for other values of N_ρ to enhance legibility of the high- Ra_F behavior. The highest-Rayleigh-number spectrum in each panel is indicated by a dashed, dark red line. Each spectrum represents a time-average over approximately 1,000 days of simulated time, corresponding to several tens of convective overturnings.

A systematic trend is visible across all cases plotted here. As Ra_F increases from an initially very low value, the integral of the kinetic-energy spectrum increases, as does the point-wise amplitude at roughly all wavenumbers. This trend is commensurate with the low- Ra_F /high- κ behavior depicted in Figures 2a,b. At sufficiently high Rayleigh number, however, power in the high- ℓ portion of the spectrum continues to increase, but the low-wavenumber end begins to diminish in power. The spectrum with the highest Ra_F in each panel (red dashed line) thus has less power at large scales than its low- Ra_F counterparts. The “low-wavenumber” end of the spectrum appears to occur in the approximate range $0 \leq \ell \leq 10$ for most simulations in this study.

This phenomenon arises naturally from the fact that at sufficiently high Rayleigh number (and sufficiently low κ), the integrated kinetic energy becomes essentially independent of the degree of diffusion. At the same time, as κ is decreased and Ra_F is increased, the flow field becomes more turbulent and develops structure on increasingly

smaller scales. Because the integral of the power spectrum is conserved, **high-wavenumber power can only come at the expense of low-wavenumber power**. This general trend is independent of depth and appears so be somewhat more pronounced for systems possessing larger values of N_ρ .

Before proceeding, we wish to emphasize that the results encapsulated by Figures 2 and 3 constitute the main points of this paper. In summary:

1. When a global stellar convection simulation is not run with sufficiently high Rayleigh number, its resulting convective flow speeds will depend on the (unphysically high) value of κ , in addition to stellar parameters such as mass and luminosity. A simulation that is not in the high- Ra_F regime of Figure 2b can be expected to yield *rms* convective amplitudes which are systematically lower than those expected in an actual star.
2. For sufficiently turbulent (high- Ra_F) convection simulations, this problem does not arise. The time-averaged, integrated kinetic energy approaches a constant value, independent of the level of diffusion employed.
3. Even in this asymptotic regime, models that correctly capture the integrated kinetic energy *may naturally overestimate low-wavenumber power* because their Rayleigh number is still orders of magnitude smaller than that of an actual star. Thus, simulated convective features that derive from large-scale motions may bear little relation to their intended stellar counterparts.

Changes in Rayleigh number also impact the spatial distribution of kinetic energy. This is most clear when considering the variation of radial velocity with depth. We have plotted the normalized *rms* vertical velocity V_r in Figure 4a. We define this quantity as




Fig. 4.— Near-surface and deep-convection-zone flow speed difference as a function of Rayleigh number and N_ρ . (a) Normalized *rms* radial velocity V_r as a function of depth for $N_\rho = 4$ and three values of Ra_F (indicated by colored lines). The difference in convective flow speed between mid and upper convection zone becomes more pronounced with increasing Ra_F . (b) Relative speed difference δV for all cases plotted as a function of Rayleigh number and N_ρ (indicated by the colored symbols). δV increases with both Ra_F and N_ρ but is most sensitive to N_ρ .

$$V_r(r) \equiv \frac{u_{rms}(r)}{\max u_{rms}}, \quad (19)$$

where u_{rms} is the *rms* vertical velocity at each radius. The mean in the *rms* is spatial and temporal; it has been taken over spherical shells and over 1,000 days of simulation time. As the Rayleigh number is increased, the variation in radial velocity across the domain increases and tends to peak near the upper boundary. We suggest that this behavior is the likely result of plumes being launched from the upper boundary layer whose thickness and gradient are both changing with Rayleigh number. At high Ra_F , the boundary layer is characterized by a sharp entropy gradient, and is thus amenable to the generation of rapid, small-scale downflow plumes. The location and width of the velocity peak are thus an indirect measure of the effective penetration depth of these plumes.

This effect is most pronounced at high Ra_F and high N_ρ , and we may quantify it by

examining the relative velocity jump δV , which we define as

$$\delta V \equiv \frac{\max u_{rms} - u_{rms}(r_{mid})}{u_{rms}(r_{mid})}, \quad (20)$$

where r_{mid} is the radial depth halfway between r_i and r_o . The relative velocity jump measured for each case is plotted in Figure 4b. The trend present in panel *a* of that figure is more clearly illustrated here. δV increases with Ra_F for all values of N_ρ studied, reaching the highest values for the $N_\rho = 4$ cases. We note that it is due to the logarithmic axes that δV appears to be asymptoting to a constant value within each N_ρ series. While the growth of δV is slowing at high Ra_F , this quantity is still clearly increasing within each series. We note further that we have not succeeded in identifying a clear scaling law linking the behavior of δV to the value of Ra_F . Nevertheless, the apparent trend suggests that a star such as the Sun, whose convection zone is characterized by much higher values of both N_ρ and Ra_F , should possess a δV greater than 4. This behavior has implications for the solar near-surface shear layer, as we discuss in §5.

4.2. Energy Transport

Rotation and magnetism aside, the convective dynamics realized in our simulations will likely differ significantly from those found within a star due to both the large values of diffusivity we employ and the conductive boundary layer that develops near the top of the domain. We have seen that diffusion plays a minimal role in the determination of the convective kinetic energy, and we now seek to quantify its role in the energy transport across the layer. The thermo-mechanical transport of energy in our system may be characterized by three radial energy fluxes, namely the enthalpy flux F_e , the kinetic energy flux F_{KE} , and the conductive flux F_c , which we define as

$$F_e = \bar{\rho} c_p \langle v_r T \rangle, \quad (21)$$

$$F_{KE} = \frac{1}{2} \bar{\rho} \langle v_r |\mathbf{v}|^2 \rangle, \quad (22)$$

and

$$F_c = \kappa \bar{\rho} \bar{T} \left\langle \frac{\partial S}{\partial r} \right\rangle \quad (23)$$

respectively. We consider averages of these quantities taken over 1,000 days of simulation time and over spherical surfaces, denoting that average by angular brackets. Thus F_e , F_{KE} , and F_c are a function of radius only. At each radius, the sum of these three fluxes must equate to the net flux F , established by the internal heating Q (Equation 12), such that

$$F(r) = F_e(r) + F_{KE}(r) + F_c(r). \quad (24)$$

We may now quantify the contribution of conduction by considering the fractional convective flux f_{conv} , which we define as

$$f_{conv} \equiv \frac{\int_V F_e + F_{KE} dV}{\int_V F dV} = 1 - \frac{\int_V F_{cond} dV}{\int_V F dV}. \quad (25)$$

A value of zero for f_{conv} indicates a lack of convective heat transport. A value of f_{conv} near unity indicates that convection plays a dominant role over thermal conduction. The variation of time-averaged f_{conv} with Rayleigh number is plotted for all simulations in Figure 5a. This quantity is clearly asymptoting toward unity as Ra_F is increased and reaches a value of 0.958 for our highest Ra_F , $N_\rho = 4$ run. Thermal conduction is thus playing a minimal role in the average transport of thermal energy at high Rayleigh number.

The role of conduction may be further characterized by considering the extent of the thermal boundary layer. We define the thermal boundary layer width in terms of the




Fig. 5.— Thermal boundary layer and energy transport scaling with Rayleigh number. (a) Fractional convective flux f_{conv} vs. Ra_F . f_{conv} approaches unity as Ra_F is increased, indicating that conduction is playing a minimal role in the energy transport. (b) Boundary layer width plotted vs. Ra_F and (c) the boundary-layer dependent Rayleigh number Ra_{BL} . The boundary layer width follows a clear scaling law of $w_{BL} \propto Ra_{BL}^{-1/6}$ (dashed line, panel c).

time-averaged mean entropy, such that

$$w_{BL} = \frac{1}{\max \langle S(r) \rangle} \int \langle S(r) \rangle dr. \quad (26)$$

The variation of w_{BL} with Rayleigh number is illustrated in Figure 5b.

The boundary layer width decreases systematically with increasing Ra_F and exhibits a clear dependence on the degree of density stratification N_ρ . At comparable Ra_F , simulations with low values of N_ρ possess a wider thermal boundary layer than those with higher values of N_ρ . This difference may be largely understood by noting that the thermal boundary layer is an upper-convection zone phenomenon and is better described by properties local to that region.

We may define an alternative formulation of the Rayleigh number, Ra_{BL} , by substituting point-wise values taken at the upper boundary for the volume-averaged quantities in Equation (14). Using this definition of the Rayleigh number, the multiple curves apparent in Figure 5b nearly collapse onto a single curve, as depicted in Figure 5c.

A fit to the scaling exponent yields the (unsurprising) relationship

$$w_{BL} \propto Ra_{BL}^{-0.169} \quad (27)$$

In other words, the boundary layer width scales very nearly as $\sqrt{\kappa}$. We note that for our highest Rayleigh number run, the boundary layer width is roughly 3 Mm, or about 2% of the shell depth. Thus, while our thermal boundary layers lack the radiative processes at work in the Sun, their physical extent is confined to a similarly small region of the convective domain.

5. Perspectives and Conclusions

Our results hold interesting consequences for several aspects of convection zone dynamics. Many of these results will undoubtedly be sensitive to the effects of rotation and magnetism which were omitted in this study. Nevertheless, we discuss some implications of this work and remark that we are now pursuing a complementary set of simulations that incorporate those effects.

5.1. Interpretation of the Kinetic Energy Scaling

The kinetic-energy scaling observed in these simulations may be understood in terms of a free-fall argument (e.g., Spiegel 1971). We outline such an argument as follows, assuming that $Pr = 1$ (as is true for the models presented here) and that the kinetic energy derives from the potential energy PE_{BL} associated with the boundary layer.

Our conductive boundary layer possesses an entropy gradient given by Equation (13) and a width that is roughly proportional to $Ra_{BL}^{-1/6}$ (i.e., $\sqrt{\kappa}$). Thus, the entropy contrast

ΔS across that layer should scale as

$$\Delta S \approx \left. \frac{\partial S}{\partial r} \right|_{r=r_o} w_{BL} \propto \frac{L_\star Ra_{BL}^{-1/6}}{4\pi r_o^2 \kappa \bar{\rho}(r_o) \bar{T}(r_o)}. \quad (28)$$

The boundary layer possesses an entropy deficit with respect to the adiabatic interior of roughly $\Delta S/2$. This entropy deficit translates into an overdensity within that region, with an associated mass M_{BL} given by

$$M_{BL} \approx \frac{\bar{\rho}(r_o)}{c_p} \frac{\Delta S}{2} \times 4\pi r_o^2 w_{BL} \propto \frac{L_\star Ra_{BL}^{-1/3}}{2\kappa c_p \bar{T}(r_o)} \quad (29)$$

The potential energy, and thus the kinetic energy associated with the convection then scales as

$$KE \approx PE_{BL} \approx M_{BL} g H \propto \left(\frac{L_\star g}{c_p \bar{T}(r_o)} \right)^{2/3} \left(\frac{4\pi r_o^2 \bar{\rho}(r_o)}{H} \right)^{1/3}, \quad (30)$$

which is independent of the thermal diffusivity owing to the two factors of $\sqrt{\kappa}$ arising from the boundary layer thickness. As we observe only a very weak dependence on diffusion in our KE scaling (see Equation 16), we suggest this is the dominant balance struck in our high- Ra_F models. This scaling appears as a common feature of high- Ra convection in the laboratory setup (see e.g., Ahlers et al. 2009 and references therein). Moreover, Boussinesq studies carried out using spherical geometry and symmetric, fixed temperature boundary conditions (in lieu of internal heating) have demonstrated a similar scaling relationship (Gastine et al. 2015).

The scaling properties of our boundary layer hold interesting consequences for extrapolation to the Sun. Perhaps it is most intuitive to think that the most realistic models of solar convection would be achieved by simulations with the same diffusivities or Rayleigh number as the Sun. However, the radiative cooling which characterizes the upper boundary layer in the Sun differs markedly from the thermal conduction employed in our models. As a result, extrapolating to the solar microscopic diffusivities may not actually reproduce the properties of solar convection. The convection in both the Sun and in our

simulations is largely driven by intense buoyancy fluctuations within the thermal boundary layer. Since, the structure of that convection is likely tied to the boundary layer’s width, it might be best to extrapolate our models to a common boundary-layer thickness.

This exercise requires far less extrapolation in parameter space because the Sun’s thermal boundary layer is only somewhat thinner than those achieved here. Our most turbulent case possesses an Ra_F of roughly 3×10^7 and a boundary layer width of about 3 Mm. Were we to seek a boundary layer width of 1 Mm, consistent with the size of a typical solar granule, we would need to decrease κ for that case by another factor of nine and increase Ra_F by a factor of about 300. While this would certainly be challenging to accomplish using modern computational resources, it is not impossible. Alternatively, convective shells embodying a higher degree of density stratification might be examined to similarly achieve a thinner boundary layer. In either case, fully spectral simulations such as these are, somewhat surprisingly, capable of resolving many of the relevant spatial scales in the solar convection zone.

If we were instead to follow our initial instinct and extrapolate our simulations to a Rayleigh number more characteristic of stellar convection zones (e.g., 10^{20}), the boundary layer would become unphysically thin. The resulting convection would likely be over-driven at small scales. It is thus possible that the convective velocity spectra achieved in these simulations is more similar to that occurring in an actual star than in a hypothetical “stellar”-Rayleigh-number case. This subtlety should be kept in mind when extrapolating results such as these to stellar-like parameter regimes. Finally, we note that the measured prefactor for our scaling is almost certainly determined by the conductive physics at work in the boundary layer, and that the implementation of radiative cooling will likely modify the amplitude of those curves illustrated in Figures 2*a,b*.

5.2. Interaction with Rotation

While our simulations were non-rotating, it is nonetheless interesting to speculate on how the behavior of the kinetic energy spectrum might impact the differential rotation. The most reliable result from helioseismology with regard to the dynamics of the deep convection zone continues to be the Sun’s internal-rotation profile obtained through global inversions of p -mode frequency splittings (e.g., Thompson et al. 2003). Such inversions indicate that the surface differential rotation possesses a variation in angular velocity (decreasing by 30% from equator to pole) that persists throughout the convection zone with little radial variation.

Because of this robust observational constraint, the onset of anti-solar differential rotation in high Ra_F , rotating convection is troubling. This behavior has been studied in a variety of stellar and astrophysical contexts, and it has been unambiguously linked to the degree of rotational influence felt by the convection (Gilman 1977; Glatzmaier & Gilman 1982; Gastine et al. 2013; Guerrero et al. 2013; Gastine et al. 2014; Käpylä et al. 2014; Featherstone & Miesch 2015). The rotational constraint felt by the convection is characterized by the Rossby number, Ro , which expresses the ratio of a rotation period to a convective time scale. It is typically defined as $Ro = u/2\Omega H$, where u is a typical convective flow speed, Ω is the rotation rate of the star, and H is some typical length scale (typically taken as the depth of the convective layer).

A transition occurs between solar and anti-solar behavior when the convective and rotational timescales become comparable, and Ro approaches unity. Alternatively, one may define a local Rossby number $Ro_\ell = u_{rms}/\Omega\ell_c$, where ℓ_c is a characteristic length scale associated with the convection (not to be confused with the spherical harmonic degree ℓ). Such a definition is equally useful for characterizing the transition between solar and anti-solar states (Gastine et al. 2014). The trend evident in the spectra of Figure 3 suggests

that ℓ_c will continue to decrease as Ra_F is increased. At the same time, our results indicate that u_{rms} will remain fixed. If this trend continues, Ro_ℓ will continue to increase as Ra_F is increased, and anti-solar states, which naturally arise at high values of Ro_ℓ , may become more prevalent.

We note that magnetism will almost certainly modify this discussion. In fact, several studies indicate that the presence of a Lorentz force, which tends to inhibit the mixing of momentum by convection, increases the transitional value of Ro in rotating systems (e.g., Fan & Fang 2014; Karak et al. 2015; Simitev et al. 2015). How those magnetic effects relate to the spectral redistribution of energy discussed here remains to be examined.

5.3. The Near-Surface Shear Layer

Our results may also hold interesting consequences for the study of the solar near-surface shear layer. That region of the convection zone, which spans the outer 5% of the Sun by radius, is characterized by a diminishment of the angular velocity established within the bulk of the convection zone (e.g., Howe 2009). Precisely how this region of shear is established is not yet completely understood, though it is likely determined by a transition from deep convection, which is thought to be rotationally-constrained, to near-surface convection, which is only weakly influenced by rotation (Miesch & Hindman 2011; Hotta et al. 2014). A number of numerical convection studies suggest that density stratification also plays an important role in the development of such a region of shear (Käpylä et al. 2011; Gastine et al. 2013; Hotta et al. 2014). One reason for this behavior may be the tendency of a background density stratification to accentuate differences in the speed of near-surface flows relative to deep flows, as shown in Figure 4*b*. Higher values of Ra_F also make this difference more pronounced (Figure 4*a*), though density stratification seems to be the dominant effect in the parameter space explored here. Our results suggest that studies

designed to systematically explore the development of a near-surface shear layer should focus on the high- N_ρ and high- Ra_F regime.

5.4. Conclusions

The results from this study indicate that care must be taken in the interpretation of simulated convective flows and, in particular, when carrying out comparisons between those flows and their solar/stellar counterparts. The numerical results discussed here illustrate one means by which stellar convection simulations may naturally overestimate the low-wavenumber power in a convective velocity spectrum. Namely, at sufficiently high Rayleigh number Ra_F , the integrated, dimensional kinetic energy saturates at a constant value. That value is independent of the level of thermal diffusion. At the same time, as diffusion is decreased and Ra_F is increased, the convection naturally develops smaller-scale structure and a corresponding increase in high-wavenumber power. As the integrated kinetic energy remains approximately constant, that high-wavenumber power must come at the expense of low-wavenumber power.

Simulations that are not run with a sufficiently high value of Ra_F will thus possess spectra that naturally disagree with the low-wavenumber measurements accessible to helioseismology. This general trend may contribute to the disagreement between simulations and the deep time-distance measurements discussed in Hanasoge et al. (2012). It is also possible that this trend may help explain the disagreement between photospheric convection simulations and the observed photospheric power spectra as discussed in Lord et al. (2014). While such photospheric convection models incorporate radiative-transfer effects that were not considered in this study, their convection is similarly constrained to transport a solar flux, and so it may develop a similar phenomenology. Those simulations also employ open boundary conditions and Cartesian geometry, however, and thus a more thorough study

of this effect needs to be carried out within that experimental setup before definitive conclusions may be drawn.

What is clear from this work is that stellar convection simulations must be run in the high-Rayleigh-number regime if they are to correctly capture even the grossest property of a star’s convection, namely the integrated kinetic energy. Unfortunately, even in the high-Rayleigh-number regime, it remains unclear how well such simulations can address the spectral distribution of that energy, particularly if they do not properly capture the scale of convective driving. For the parameter space explored here, the spectral range $\ell \leq 10$ appears to represent a particularly sensitive region of the power spectrum.

We conclude by noting that only relatively modest values of diffusion ($\kappa \leq 4 \times 10^{12} \text{ cm}^2 \text{ s}^{-1}$) are required to reach the high-Rayleigh number regime identified here. However, virtually all stellar convection simulations incorporate rotation, and many now incorporate magnetism. Our simulations incorporated neither. The inclusion of those effects will almost certainly increase the critical Rayleigh number of the system (e.g., Chandrasekhar 1961), and so too the lower limit of the high-Rayleigh-number regime. It is thus timely to examine how magnetism and rotation modify these findings, and then assess where current models lie within the framework discussed here. In the interim, the utility of detailed spectral comparisons between observations and simulations will remain questionable.

We wish to thank Mark Miesch and Juri Toomre for several useful discussions over the years that helped to frame the central question posed in this work. We further wish to thank Keith Julien for his many thoughtful comments that substantially improved the presentation of these results. Finally, we wish to thank the staff at NASA Pleiades, NASA Discover, and the Argonne Leadership Computing Facility (ALCF; particularly Wei Jiang), without whom these simulations would not have been possible.

This work was supported by NASA grants NNX09AB04G, NNX14AC05G, NNX11AJ36G, and NNX14AG05G. Featherstone and the development of *Rayleigh* were further supported by the Computational Infrastructure for Geodynamics (CIG), which is supported by the National Science Foundation award NSF-094946. This work used computational resources provided through NASA HEC support on the Pleiades and Discover supercomputers. Further support was provided by an award of computer time on the Mira supercomputer through the Innovative and Novel Computational Impact on Theory and Experiment (INCITE) program. This research used resources of the ALCF, which is a DOE Office of Science User Facility supported under Contract DE-AC02-06CH11357.

A. Algorithmic Accuracy Considerations

The accuracy with which *Rayleigh* solves the system of equations enumerated in §2 may be assessed by carrying out the benchmark exercises described in Jones et al. (2011). We report on results from the steady hydrodynamic and magnetohydrodynamic benchmark exercises described in that work. Those solutions each possess a convective pattern that is comprised of a single, sectoral spherical harmonic mode. That pattern is temporally steady save for a uniform drift with respect to the rotating frame.

The accuracy of a code may be checked by measuring the drift rate of the convective pattern, various components of the energy associated with that pattern, and by computing point-wise measurements of flow variables such as velocity, entropy, and magnetic field. We provide a summary of the results obtained by *Rayleigh* in Tables A.1 and A.2 below. For reference, we also provide representative values from those reported in Jones et al. (2011). Specifically, we provide the values achieved by the Glatzmaier code, along with relative differences between the Glatzmaier results and the *Rayleigh* results. *Rayleigh's* results typically agree with the accepted benchmark results to within one tenth of one percent.

TABLE A.1
Anelastic MHD Benchmark Results

Observable	Rayleigh	Glatzmaier	% Difference
Kinetic Energy (erg)	5.56967×10^{35}	5.57028×10^{35}	-1.09510×10^{-2}
Zonal Kinetic Energy (erg)	6.37973×10^{34}	6.38099×10^{34}	-1.97462×10^{-2}
Meridional Kinetic Energy (erg)	1.49799×10^{32}	1.49825×10^{32}	-1.73536×10^{-2}
Entropy (erg g ⁻¹ K ⁻¹)	7.9449×10^5	7.9452×10^5	-3.7759×10^{-3}
u_ϕ (cm s ⁻¹)	6.8638×10^2	6.9027×10^2	-5.6355×10^{-1}
Drift Frequency (rad s ⁻¹)	3.10509×10^{-6}	3.10512×10^{-6}	-9.6615×10^{-4}

Note. — Hydrodynamic benchmark results for *Rayleigh*. The simulation was run with a resolution of $128 \times 192 \times 384$ ($N_r \times N_\theta \times N_\phi$), corresponding to 96 Chebyshev modes and a maximum spherical harmonic degree of 127. All quantities reported were averaged over 10,000 time steps following equilibration of the steady-state solution. The time step size was 30 seconds, and the total evolution time was 4.8×10^6 seconds.

TABLE A.2
Anelastic MHD Benchmark Results

Observable	Rayleigh	Glatzmaier	% Difference
Kinetic Energy (erg)	8.03633×10^{36}	8.03623×10^{36}	1.24436×10^{-3}
Zonal KE (erg)	1.15320×10^{36}	1.15318×10^{36}	1.73433×10^{-3}
Meridional KE (erg)	1.01585×10^{33}	1.01587×10^{33}	-1.96876×10^{-3}
Magnetic Energy (erg)	6.13362×10^{36}	6.13333×10^{36}	4.72826×10^{-3}
Zonal ME (erg)	4.62063×10^{36}	4.62046×10^{36}	3.67929×10^{-3}
Meridional ME (erg)	3.24922×10^{36}	3.24927×10^{36}	-1.53881×10^{-3}
Entropy (erg g ⁻¹ K ⁻¹)	6.0886×10^5	6.0893×10^5	-4.4340×10^{-2}
u_ϕ (cm s ⁻¹)	-2.9374×10^3	-2.9422×10^3	-1.6314×10^{-1}
B_θ (G)	2.7187×10^2	2.7292×10^2	-3.8473×10^{-1}
Drift Frequency (rad s ⁻¹)	4.3075×10^{-6}	4.3076×10^{-6}	-2.3215×10^{-3}

Note. — Hydrodynamic benchmark results for *Rayleigh*. The simulation was run with a resolution of $128 \times 192 \times 384$ ($N_r \times N_\theta \times N_\phi$), corresponding to 96 Chebyshev modes and a maximum spherical harmonic degree of 127. All quantities reported were averaged over 10,000 time steps following equilibration of the steady-state solution. The time step size was 200 seconds, and the total evolution time was 5×10^8 seconds.

B. Summary of Model Parameters and Results

In the four tables that follow, we report on the input and output parameters from our set of 63 simulations. A separate table of parameters is presented for each value of N_ρ used in this study. Each simulation is specified by three physical input parameters: the thermal diffusivity κ , the luminosity of the simulation L_\star , and the bulk flux Rayleigh number Ra_F as defined by Equation (14). We report the thermal diffusivity κ in units of $10^{12} \text{ cm}^2 \text{ s}^{-1}$, denoting it by κ_{12} in these tables. Similarly, we report luminosities that have been normalized by the solar luminosity $L_\odot = 3.846 \times 10^{33} \text{ erg s}^{-1}$. Additionally, we report on the resolution used in each simulation, listing the maximum spherical harmonic and Chebyshev polynomial degrees employed (ℓ_{max} and n_{max} respectively). All variables have been de-aliased using the 2/3 rule. The number of collocation points in radius N_R is given by $N_R = \frac{3}{2}(n_{max} + 1)$. Similarly, the number of collocation points in theta N_θ is given by $N_\theta = \frac{3}{2}(\ell_{max} + 1)$. The number of azimuthal points N_ϕ is always twice N_θ .

We also report on the measured outputs for each simulation. These are the dimensional kinetic energy KE , the non-dimensional kinetic energy \widehat{KE} , the relative velocity difference δV , the fractional convective flux f_{conv} , and the boundary layer width w_{BL} . Definitions for these values are provided in Equations (15), (17), (20), (25), and (26) respectively. Finally, while not discussed in this paper, we report on two Reynolds numbers measured for each simulation. The first is the bulk Reynolds number, which we denote by Re and define as

$$Re = \frac{\sqrt{|\tilde{\mathbf{v}}|^2} H}{\nu}, \quad (\text{B1})$$

where H and the tilde retain the same meaning as in the rest of this paper, representing the shell depth and a volume average respectively. The density stratification employed in these simulations means that the velocity amplitude varies substantially throughout the shell. As

such, we also report the peak Reynolds number Re_{peak} , which we define as

$$Re_{peak} = \frac{\max v_{rms}(r)H}{\nu}, \quad (\text{B2})$$

where v_{rms} is the *rms* velocity amplitude calculated at each depth. Both measures of the velocity were averaged in time over 1,000 days.

Table B.1: $N_\rho = 1$ Simulation Parameters

Input Parameters					Measured Output						
κ_{12}	L_\star/L_\odot	Ra_F	n_{max}	ℓ_{max}	KE	\widehat{KE}	δV	f_{conv}	w_{BL}	Re	Re_{peak}
					(10^{38} erg)	(Mm)					
0.5	1.00	3.24×10^7	85	1023	26.99	36,649.8	0.082	0.934	6.47	271.7	355.1
1	1.00	4.05×10^6	85	511	25.41	8,626.2	0.056	0.894	9.32	130.5	167.0
2	1.00	5.07×10^5	85	255	23.86	2,025.1	0.027	0.830	14.09	63.3	77.7
4	1.00	6.33×10^4	85	255	19.82	420.5	0.013	0.725	20.00	29.0	36.3
8	1.00	7.92×10^3	85	255	10.66	56.5	0.012	0.533	26.02	10.8	15.2
9	1.00	5.56×10^3	85	127	8.77	36.7	0.013	0.469	29.13	8.7	12.3
10	1.00	4.05×10^3	85	127	6.95	23.6	0.015	0.379	33.91	6.9	9.9
11	1.00	3.05×10^3	85	127	5.12	14.4	0.013	0.345	35.35	5.4	7.9
12	1.00	2.35×10^3	85	127	3.62	8.5	0.014	0.249	39.42	4.2	6.2
13	1.00	1.84×10^3	85	127	2.21	4.4	0.015	0.166	42.37	3.0	4.3

Table B.2: $N_p = 2$ Simulation Parameters

Input Parameters					Measured Output						
κ_{12}	L_\star/L_\odot	Ra_F	n_{max}	ℓ_{max}	KE	\widehat{KE}	δV	f_{conv}	w_{BL}	Re	Re_{peak}
					(10^{38} erg)	(Mm)					
1	1.00	1.23×10^7	85	511	34.67	16,095.4	0.416	0.932	6.80	189.4	243.2
2	1.00	1.54×10^6	85	255	33.08	3,839.6	0.310	0.887	9.66	91.9	120.0
4	1.00	1.93×10^5	85	255	30.92	897.0	0.179	0.807	13.86	44.8	60.8
8	1.00	2.41×10^4	85	255	23.94	173.6	0.084	0.689	19.65	20.5	30.1
9	1.00	1.69×10^4	85	85	20.28	116.3	0.091	0.644	19.70	16.7	24.2
10	1.00	1.23×10^4	85	85	19.41	90.1	0.073	0.620	21.62	15.0	23.5
11	1.00	9.28×10^3	85	85	17.25	66.2	0.102	0.565	21.62	12.5	18.5
12	1.00	7.14×10^3	85	85	15.53	50.1	0.099	0.526	22.72	10.9	16.3
13	1.00	5.62×10^3	85	85	12.71	34.9	0.087	0.500	24.15	9.3	15.3
14	1.00	4.50×10^3	85	85	10.84	25.7	0.099	0.422	25.97	7.8	12.4
15	1.00	3.66×10^3	85	85	8.99	18.6	0.100	0.382	27.17	6.9	10.9
16	1.00	3.01×10^3	85	85	7.06	12.8	0.106	0.330	28.79	5.5	9.3
17	1.00	2.51×10^3	85	85	5.64	9.1	0.118	0.290	29.75	4.7	8.2
18	1.00	2.12×10^3	85	85	3.33	4.8	0.115	0.194	32.23	3.5	5.9
19	1.00	1.80×10^3	85	85	2.36	3.0	0.111	0.139	33.50	2.7	4.6
20	1.00	1.54×10^3	85	85	1.16	1.3	0.104	0.074	34.89	1.8	3.1

Table B.3: $N_\rho = 3$ Simulation Parameters

Input Parameters					Measured Output						
κ_{12}	L_\star/L_\odot	Ra_F	n_{max}	ℓ_{max}	KE	\widehat{KE}	δV	f_{conv}	w_{BL}	Re	Re_{peak}
					(10^{38} erg)	(Mm)					
1	1.00	2.14×10^7	85	1023	36.22	20,057.7	1.323	0.948	4.96	229.8	320.4
2	1.00	2.68×10^6	85	511	34.73	4,807.6	1.094	0.912	6.93	114.1	166.5
4	1.00	3.35×10^5	85	263	33.42	1,156.7	0.799	0.847	9.83	56.3	85.6
6	1.00	9.93×10^4	85	127	32.92	506.4	0.617	0.791	12.18	37.5	58.2
8	1.00	4.19×10^4	85	127	31.62	273.5	0.452	0.736	14.09	27.5	42.4
12	1.00	1.24×10^4	85	127	22.08	84.9	0.275	0.623	16.03	15.4	24.0
16	1.00	5.23×10^3	42	127	12.02	26.0	0.266	0.442	19.06	9.0	15.6
24	1.00	1.55×10^3	42	63	2.05	2.0	0.198	0.122	23.77	2.5	4.5
0.5	0.19	3.25×10^7	170	85	12.27	27,173.6	1.353	0.953	4.65	265.3	363.5
1	0.29	6.16×10^6	85	1023	15.37	8,512.9	1.189	0.929	6.03	151.4	215.8
2	0.44	1.17×10^6	85	511	19.68	2,723.7	1.011	0.890	7.93	86.5	129.8
4	0.66	2.21×10^5	85	263	25.39	878.7	0.710	0.830	10.60	49.0	74.4
6	0.84	8.35×10^4	85	127	28.96	445.4	0.562	0.781	12.70	35.3	55.0
1	0.12	2.68×10^6	85	1023	8.71	4,820.8	1.096	0.912	6.94	113.8	166.1
2	0.25	6.70×10^5	85	511	13.44	1,860.7	0.898	0.873	8.75	71.2	105.9
4	0.50	1.68×10^5	85	263	21.00	726.7	0.713	0.815	11.09	44.3	68.5
6	0.75	7.44×10^4	85	127	27.12	417.1	0.545	0.773	12.85	34.2	52.7

Table B.4: $N_\rho = 4$ Simulation Parameters

Input Parameters					Measured Output						
κ_{12}	L_\star/L_\odot	Ra_F	n_{max}	ℓ_{max}	KE	\widehat{KE}	δV	f_{conv}	w_{BL}	Re	Re_{peak}
					(10^{38} erg)	(Mm)					
1	1.00	2.84×10^7	170	1023	34.38	20,892.4	3.216	0.958	3.37	254.0	388.4
2	1.00	3.55×10^6	85	511	32.21	4,892.5	2.691	0.925	4.66	124.2	193.0
4	1.00	4.43×10^5	85	511	30.91	1,173.8	1.961	0.864	6.63	61.5	98.3
8	1.00	5.54×10^4	85	255	29.49	280.0	1.145	0.755	9.42	29.9	48.5
9	1.00	3.89×10^4	85	127	29.04	217.9	1.060	0.732	9.99	26.5	43.5
10	1.00	2.84×10^4	85	127	28.72	174.5	0.901	0.712	10.54	23.5	38.3
11	1.00	2.13×10^4	85	127	27.03	135.7	0.800	0.688	11.00	20.9	34.2
12	1.00	1.64×10^4	85	127	25.64	108.2	0.697	0.661	11.47	18.8	31.1
13	1.00	1.29×10^4	85	127	22.53	81.0	0.479	0.624	11.99	16.4	27.6
14	1.00	1.03×10^4	85	127	20.44	63.4	0.410	0.594	12.32	14.6	24.9
15	1.00	8.41×10^3	85	127	18.45	49.8	0.409	0.557	12.57	13.0	22.2
16	1.00	6.93×10^3	85	127	16.32	38.7	0.383	0.522	12.81	11.6	20.0
17	1.00	5.78×10^3	85	85	14.18	29.8	0.380	0.486	13.04	10.2	18.0
18	1.00	4.87×10^3	85	85	12.38	23.2	0.410	0.436	13.37	9.2	16.3
19	1.00	4.14×10^3	85	85	10.40	17.5	0.379	0.393	13.62	7.9	14.3
20	1.00	3.55×10^3	85	85	7.21	10.9	0.177	0.336	14.09	6.4	12.5
21	1.00	3.06×10^3	85	85	5.49	7.6	0.186	0.270	14.50	5.3	10.4
22	1.00	2.67×10^3	85	85	3.69	4.6	0.196	0.196	15.01	4.2	8.3
23	1.00	2.33×10^3	85	85	3.10	3.6	0.498	0.180	15.03	3.8	7.2
24	1.00	2.05×10^3	85	85	2.96	3.1	0.475	0.166	15.15	3.4	6.5

C. Polytropic Background State

For these experiments, we employ a polytropic background state as formulated in the anelastic benchmark paper of Jones et al. (2011). We assume that the gravitational acceleration $g(r)$ varies as GM_i/r^2 within the shell, where M_i is the mass interior to the base of the convection zone and G is the gravitational constant. The anelastic equations then admit an adiabatically stratified, polytropic atmosphere as the reference state:

$$\rho_0 = \rho_i \left(\frac{\zeta}{\zeta_i} \right)^n, \quad T_0 = T_i \frac{\zeta}{\zeta_i}, \quad p_0 = p_i \left(\frac{\zeta}{\zeta_i} \right)^{n+1}, \quad (\text{C1})$$

where the subscript “ i ” denotes the value of a quantity at the inner boundary, and n is the polytropic index. The radial variation of the reference state is captured by the variable ζ , defined as

$$\zeta = c_0 + \frac{c_1 H}{r}, \quad (\text{C2})$$

where $H = r_o - r_i$ is the depth of the convection zone. The constants c_0 and c_1 are given by

$$c_0 = \frac{2\zeta_o - \beta - 1}{1 - \beta}, \quad c_1 = \frac{(1 + \beta)(1 - \zeta_o)}{(1 - \beta)^2}, \quad (\text{C3})$$

with

$$\zeta_o = \frac{\beta + 1}{\beta \exp(N_\rho/n) + 1}, \quad \zeta_i = \frac{1 + \beta - \zeta_o}{\beta}. \quad (\text{C4})$$

Here ζ_i and ζ_o are the values of ζ on the inner and outer boundaries, $\beta = r_i/r_o$, and N_ρ is the number of density scale heights across the shell.

REFERENCES

- Ahlers, G., Grossmann, S. & Lohse, D., 2009, *RvMP*, 81, 503
- Braginsky, S.I., Roberts, P.H., 1995, *GAFD*, 79, 1
- Brun, A.S. & Toomre, J., 2002, *ApJ*, 570, 865
- Brun, A.S., Miesch, M.S. & Toomre, J., 2004, *ApJ*, 614, 1073
- Chandrasekhar, S., 1961, *Hydrodynamic and Hydromagnetic Stability* (Oxford: Clarendon)
- Charbonneau, P., 2010, *LRSP*, 7, 3
- Christensen-Dalsgaard, J., et al. 1996, *Science*, 272, 1286
- Fan, Y. & Fang, F., 2014, *ApJ*, 789, 35
- Featherstone, N.A. & Miesch, M.S., 2015, *ApJ*, 804, 67
- Gastine, T., Wicht, J. & Aurnou, J.M., 2013, *Icar* 225, 156
- Gastine, T., Yadav, R.K., Morin, J., Reiners, A. & Wicht, J., 2014, *MNRAS*, 438, L76
- Gastine, T., Wicht, J. & Aurnou, J.M., *JFM*, 778, 721
- Ghizaru, M., Charbonneau, P. & Smolarkiewicz, P.K., 2010, *ApJL*, 715, L133
- Gilman, P.A., 1977, *GApFD*, 8, 93
- Gilman, P.A. & Glatzmaier, G.A., 1981, *ApJS*, 45, 335
- Glatzmaier, G.A., 1984, *J. Comp. Phys.* 55, 461
- Glatzmaier, G.A. & Gilman, P.A., 1982, *ApJS*, 256, 316
- Gough, D.O., 1969, *JAtS*, 26, 448

- Greer, B.J., Hindman, B.W., Featherstone, N.A. & Toomre, J., 2015, ApJL, 803, 17
- Guerrero, G., Smolarkiewicz, P.K., Kosovichev, A.G. & Mansour, N.N., 2013, ApJ, 779, 176
- Hanasoge, S.M., Duvall, T.L., Jr. & Sreenivasan, K.R., 2012, PNAS, 109, 11928
- Hotta, H., Rempel, M. & Yokoyama, T., 2015, 798, 51
- Howe, R., 2009, LRSP, 6, 1
- Jones, C.A., Boronski, P., Brun, A.S., Glatzmaier, G.A., Gastine, T. Miesch, M.S. & Wicht, J., 2011, Icarus, 216,120
- Jouve, L. & Brun, A.S., 2007, A&A, 474, 239
- Käpylä, P., Mantere, M. & Brandenburg, A., 2011, AN, 332, 883
- Käpylä, P., Mantere, M. & Brandenburg, A., 2014, A&A, 570, 43
- Karak, B.B., Käpylä, P.J., Käpylä, M.J., Brandenburg, A., Olsper, N. & Pelt, J., 2015, A&A, 576, 26
- Kővári, Zs., Bartus, J., Strassmeier, K.G., Vida, K., Švanda, M. & Oláh, K. , 2007, A&A, 474, 165
- Lantz, S.R., 1992, *Dynamical Behavior of Magnetic Fields in a Stratified, Convecting Fluid Layer*, Ph.D. Thesis, Cornell Univ.
- Lord, J.W., cameron, R.H., Rast, M.P., Rempel, M. & Roudier, T., 2014, ApJ, 793, 24
- Miesch, M.S., Brun, A.S. & Toomre, J., 2006, ApJ, 641, 618
- Miesch, M.S, Brun, A.S., DeRosa, M.L. & Toomre, J., 2008, ApJ, 673, 557
- Miesch, M.S. & Hindman, B.W., 2011, ApJ, 743, 79

- Moffatt, H.K., 1978, Magnetic Field Generation in Electrically Conducting Fluids
(Cambridge: Cambridge Univ. Press)
- Ossendrijver, M., 2003, A&AR, 11, 287
- Simitev, R.D., Kosovichev, A.G. & Busse, F.H., 2015, ApJ, 810, 80
- Spiegel, E.A., 1971, ARA&A, 9, 323
- Thompson, M.J., Christensen-Dalsgaard, J., Miesch, M.S. & Toomre, J., 2003, ARA&A,
41, 599
- Zhao, J., Bogart, R.S., Kosovichev, A.G., Duvall, T.L., Jr. & Hartlep, T., 2013, ApJL, 774,
29L